



Pan Unit Benefits

- ***3"X3"X1/4" curb angles provide reliable strength at the edge of the pan***
- ***Saves time and money over conventional pours***
- ***Electrical cut outs for powered docks are included in the pan design***
- ***Unit is secured to a floor slab, back filled and poured into the finished floor***
- ***All concrete studs are in place for strong interlacing with the concrete pre-slab***
- ***Unit is pre-finished in machinery grey***
- ***Pan kit is standard dock pit size allowing levelers to be easily removed and replaced***
- ***Comes in all standard sizes 6'X6', 6.5'X6', 7'x6', 6'X8', 6.5'X 8', 7'X8'***
- ***Can be ordered in specialty sizes 10' 12'***
- ***Allows instant use of the leveler***
- ***Only bumper install needed***
- ***Fastest way to gain access to new docks***